

Company: Company
Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)
File: C:\IE REGIDOR\MOD5.rcb

Engineer: Name
9:31:45 a. m. 27/06/2025

GENERAL INPUT DATA

Structure type: Three-Dimensional Frame Structure
Number of Floor Grids = 1
Building total length = 65.52 m
Building total width = 11.62 m

STORY INFORMATION

Number of Stories = 1
Total Frame Height = 3.05 m

Floor	Story Height	Grid No
1	3.05	1
2	-	1

* Story Height in (m)

STRUCTURAL GRID INFORMATION

GRID No 1

Grid Point	X	Y
B'-6	0.00	0.00
C-6	0.00	2.24
A-6	0.00	10.30
A'-6	0.00	11.62
B'-1'	1.85	0.00
C-1'	1.85	2.24
A-1'	1.85	10.30
A'-1'	1.85	11.62
B'-8	3.70	0.00
C-8	3.70	2.24
A-8	3.70	10.30
A'-8	3.70	11.62
B'-2'	5.81	0.00
C-2'	5.81	2.24
A-2'	5.81	10.30
A'-2'	5.81	11.62
B'-3'	7.92	0.00
C-3'	7.92	2.24
A-3'	7.92	10.30
A'-3'	7.92	11.62
B'-4'	10.03	0.00
C-4'	10.03	2.24
A-4'	10.03	10.30
A'-4'	10.03	11.62
B'-12	12.14	0.00
C-12	12.14	2.24
A-12	12.14	10.30
A'-12	12.14	11.62
B'-5'	14.35	0.00
C-5'	14.35	2.24
A-5'	14.35	10.30
A'-5'	14.35	11.62
B'-13	16.56	0.00
C-13	16.56	2.24
A-13	16.56	10.30
A'-13	16.56	11.62
B'-6'	18.77	0.00
C-6'	18.77	2.24
A-6'	18.77	10.30
A'-6'	18.77	11.62
B'-15	20.98	0.00
C-15	20.98	2.24
A-15	20.98	10.30
A'-15	20.98	11.62
B'-7'	23.08	0.00
C-7'	23.08	2.24
A-7'	23.08	10.30
A'-7'	23.08	11.62
B'-8'	25.18	0.00
C-8'	25.18	2.24
A-8'	25.18	10.30
A'-8'	25.18	11.62
B'-9'	27.28	0.00
C-9'	27.28	2.24
A-9'	27.28	10.30
A'-9'	27.28	11.62
B'-16	29.38	0.00

Company: Company

Engineer: Name

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

9:31:45 a. m. 27/06/2025

Grid Point	X	Y
C-16	29.38	2.24
A-16	29.38	10.30
A'-16	29.38	11.62
B'-10'	31.51	0.00
C-10'	31.51	2.24
A-10'	31.51	10.30
A'-10'	31.51	11.62
B'-11'	33.64	0.00
C-11'	33.64	2.24
A-11'	33.64	10.30
A'-11'	33.64	11.62
B'-12'	35.77	0.00
C-12'	35.77	2.24
A-12'	35.77	10.30
A'-12'	35.77	11.62
B'-17	37.90	0.00
C-17	37.90	2.24
A-17	37.90	10.30
A'-17	37.90	11.62
B'-13'	40.02	0.00
C-13'	40.02	2.24
A-13'	40.02	10.30
A'-13'	40.02	11.62
B'-14'	42.14	0.00
C-14'	42.14	2.24
A-14'	42.14	10.30
A'-14'	42.14	11.62
B'-19	44.26	0.00
C-19	44.26	2.24
A-19	44.26	10.30
A'-19	44.26	11.62
B'-15'	46.36	0.00
C-15'	46.36	2.24
A-15'	46.36	10.30
A'-15'	46.36	11.62
B'-16'	48.46	0.00
C-16'	48.46	2.24
A-16'	48.46	10.30
A'-16'	48.46	11.62
B'-17'	50.56	0.00
C-17'	50.56	2.24
A-17'	50.56	10.30
A'-17'	50.56	11.62
B'-24	52.66	0.00
C-24	52.66	2.24
A-24	52.66	10.30
A'-24	52.66	11.62
B'-18'	54.87	0.00
C-18'	54.87	2.24
A-18'	54.87	10.30
A'-18'	54.87	11.62
B'-27	57.08	0.00
C-27	57.08	2.24
A-27	57.08	10.30
A'-27	57.08	11.62
B'-19'	59.19	0.00
C-19'	59.19	2.24
A-19'	59.19	10.30
A'-19'	59.19	11.62
B'-20'	61.30	0.00
C-20'	61.30	2.24
A-20'	61.30	10.30
A'-20'	61.30	11.62
B'-21'	63.41	0.00
C-21'	63.41	2.24
A-21'	63.41	10.30
A'-21'	63.41	11.62
B'-31	65.52	0.00
C-31	65.52	2.24
A-31	65.52	10.30
A'-31	65.52	11.62

* Coordinates X & Y are in (m)

Company: Company

Engineer: Name

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

9:31:45 a. m. 27/06/2025

MATERIALS

Number of materials = 2

REINFORCED CONCRETE

Mat	Name	f'c Kg/cm2	fy Kg/cm2	fys1 Kg/cm2	fys2 Kg/cm2	E Kg/cm2	G Kg/cm2	w Kg/m3
1	RConcrete1	210	4200	4200	4200	218540	87430	2400.0
2	RConcrete2	280	4200	4200	4200	252350	100940	2400.0

f'c: Compressive strength of concrete

fy: Yield strength of longitudinal reinforcement

fys1: Yiel strength of shear reinforcement, bar sizes <= 3/8"

fys2: Yiel strength of shear reinforcement, bar sizes > 3/8"

MEMBER DATA

Total number of members..... = 221

Number of columns..... = 22

Number of beams = 230

Number of braces = 0

COLUMN SECTIONS

Number of prismatic sections = 1

Sec	Name	Shape	b (cm)	h (cm)	tw (cm)	tf (cm)	P1 (cm)	P2 (cm)	A (cm2)	I2 (cm4)	I3 (cm4)	J (cm4)
1	C-30X50	Rectang	30.00	50.00	-	-	-	-	1500.0	312500	112500	279900

COLUMNS

Column	Story	L (m)	Lu (m)	a (m)	c (m)	Theta (o)	Sec -	Mat -	System -
A-31	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-31	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-27	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-27	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-24	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-24	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-19	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-19	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-17	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-17	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-16	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-16	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-15	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-15	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-13	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-13	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-12	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-12	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-8	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L

Company: Company

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

Engineer: Name

9:31:45 a. m. 27/06/2025

Column	Story	L	Lu	a	c	Theta	Sec	Mat	System
C-8	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
A-6	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L
C-6	1	3.05	2.53	0.00	0.53	0.0	1	2	G&L

BEAM SECTIONS

Number of prismatic sections = 3

Sec	Name	Shape	b (cm)	h (cm)	tw (cm)	tf (cm)	P1 (cm)	P2 (cm)	A (cm2)	I2 (cm4)	I3 (cm4)	J (cm4)
1	VG-30X60	Rectang	30.00	60.00	-	-	-	-	1800.0	540000	135000	369900
2	VG-20X60	Rectang	20.00	60.00	-	-	-	-	1200.0	360000	40000	126400
3	VC-30X45	Rectang	30.00	45.00	-	-	-	-	1350.0	227812	101250	234900

BEAMS

Beam	Floor	L (m)	Lu (m)	a (m)	c (m)	Sec	Mat	System
C (6-8)	1	3.70	3.40	0.15	0.15	3	2	G&L
C (8-12)	1	8.44	8.14	0.15	0.15	3	2	G&L
C (12-13)	1	4.42	4.12	0.15	0.15	3	2	G&L
C (13-15)	1	4.42	4.12	0.15	0.15	3	2	G&L
C (15-16)	1	8.40	8.10	0.15	0.15	3	2	G&L
C (16-17)	1	8.52	8.22	0.15	0.15	3	2	G&L
C (17-19)	1	6.36	6.06	0.15	0.15	3	2	G&L
C (19-24)	1	8.40	8.10	0.15	0.15	3	2	G&L
C (24-27)	1	4.42	4.12	0.15	0.15	3	2	G&L
C (27-31)	1	8.44	8.14	0.15	0.15	3	2	G&L
A (6-8)	1	3.70	3.40	0.15	0.15	3	2	G&L
A (8-12)	1	8.44	8.14	0.15	0.15	3	2	G&L
A (12-13)	1	4.42	4.12	0.15	0.15	3	2	G&L
A (13-15)	1	4.42	4.12	0.15	0.15	3	2	G&L
A (15-16)	1	8.40	8.10	0.15	0.15	3	2	G&L
A (16-17)	1	8.52	8.22	0.15	0.15	3	2	G&L
A (17-19)	1	6.36	6.06	0.15	0.15	3	2	G&L
A (19-24)	1	8.40	8.10	0.15	0.15	3	2	G&L
A (24-27)	1	4.42	4.12	0.15	0.15	3	2	G&L
A (27-31)	1	8.44	8.14	0.15	0.15	3	2	G&L
B' (6-1')	2	1.85	1.70	0.15	0.00	2	2	G
B' (1'-8)	2	1.85	1.70	0.00	0.15	2	2	G
B' (8-2')	2	2.11	1.96	0.15	0.00	2	2	G
B' (2'-3')	2	2.11	2.11	0.00	0.00	2	2	G
B' (3'-4')	2	2.11	2.11	0.00	0.00	2	2	G
B' (4'-12)	2	2.11	1.96	0.00	0.15	2	2	G
B' (12-5')	2	2.21	2.06	0.15	0.00	2	2	G
B' (5'-13)	2	2.21	2.06	0.00	0.15	2	2	G
B' (13-6')	2	2.21	2.06	0.15	0.00	2	2	G
B' (6'-15)	2	2.21	2.06	0.00	0.15	2	2	G
B' (15-7')	2	2.10	1.95	0.15	0.00	2	2	G
B' (7'-8')	2	2.10	2.10	0.00	0.00	2	2	G
B' (8'-9')	2	2.10	2.10	0.00	0.00	2	2	G
B' (9'-16)	2	2.10	1.95	0.00	0.15	2	2	G
B' (16-10')								
B' (10'-11')	2	2.13	1.98	0.15	0.00	2	2	G
B' (11'-12')	2	2.13	2.13	0.00	0.00	2	2	G
B' (12'-17)	2	2.13	2.13	0.00	0.00	2	2	G
B' (17-13')	2	2.13	1.98	0.00	0.15	2	2	G
B' (13'-14')	2	2.12	1.97	0.15	0.00	2	2	G
B' (14'-19)	2	2.12	2.12	0.00	0.00	2	2	G
B' (19-15')	2	2.12	1.97	0.00	0.15	2	2	G
B' (15'-16')	2	2.10	1.95	0.15	0.00	2	2	G
B' (16'-17')	2	2.10	2.10	0.00	0.00	2	2	G
	2	2.10	2.10	0.00	0.00	2	2	G

Company: Company

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

Engineer: Name

9:31:45 a. m. 27/06/2025

Beam	Floor	L	Lu	a	c	Sec	Mat	System
B' (17'-24)								
B' (24-18')	2	2.10	1.95	0.00	0.15	2	2	G
B' (18'-27)	2	2.21	2.06	0.15	0.00	2	2	G
B' (27-19')	2	2.21	2.06	0.00	0.15	2	2	G
B' (19'-20')	2	2.11	1.96	0.15	0.00	2	2	G
B' (20'-21')	2	2.11	2.11	0.00	0.00	2	2	G
B' (21'-31)	2	2.11	2.11	0.00	0.00	2	2	G
C (6-1')	2	2.11	1.96	0.00	0.15	2	2	G
C (1'-8)	2	1.85	1.70	0.15	0.00	1	2	G&L
C (8-2')	2	1.85	1.70	0.00	0.15	1	2	G&L
C (2'-3')	2	2.11	1.96	0.15	0.00	1	2	G&L
C (3'-4')	2	2.11	2.11	0.00	0.00	1	2	G&L
C (4'-12)	2	2.11	2.11	0.00	0.00	1	2	G&L
C (12-5')	2	2.11	1.96	0.00	0.15	1	2	G&L
C (5'-13)	2	2.21	2.06	0.15	0.00	1	2	G&L
C (13-6')	2	2.21	2.06	0.00	0.15	1	2	G&L
C (6'-15)	2	2.21	2.06	0.00	0.15	1	2	G&L
C (15-7')	2	2.10	1.95	0.15	0.00	1	2	G&L
C (7'-8')	2	2.10	2.10	0.00	0.00	1	2	G&L
C (8'-9')	2	2.10	2.10	0.00	0.00	1	2	G&L
C (9'-16)	2	2.10	1.95	0.00	0.15	1	2	G&L
C (16-10')	2	2.13	1.98	0.15	0.00	1	2	G&L
C (10'-11')	2	2.13	2.13	0.00	0.00	1	2	G&L
C (11'-12')	2	2.13	2.13	0.00	0.00	1	2	G&L
C (12'-17)	2	2.13	1.98	0.00	0.15	1	2	G&L
C (17-13')	2	2.12	1.97	0.15	0.00	1	2	G&L
C (13'-14')	2	2.12	2.12	0.00	0.00	1	2	G&L
C (14'-19)	2	2.12	1.97	0.00	0.15	1	2	G&L
C (19-15')	2	2.10	1.95	0.15	0.00	1	2	G&L
C (15'-16')	2	2.10	2.10	0.00	0.00	1	2	G&L
C (16'-17')	2	2.10	2.10	0.00	0.00	1	2	G&L
C (17'-24)	2	2.10	1.95	0.00	0.15	1	2	G&L
C (24-18')	2	2.21	2.06	0.15	0.00	1	2	G&L
C (18'-27)	2	2.21	2.06	0.00	0.15	1	2	G&L
C (27-19')	2	2.11	1.96	0.15	0.00	1	2	G&L
C (19'-20')	2	2.11	2.11	0.00	0.00	1	2	G&L
C (20'-21')	2	2.11	2.11	0.00	0.00	1	2	G&L
C (21'-31)	2	2.11	1.96	0.00	0.15	1	2	G&L
A (6-1')	2	1.85	1.70	0.15	0.00	1	2	G&L
A (1'-8)	2	1.85	1.70	0.00	0.15	1	2	G&L
A (8-2')	2	2.11	1.96	0.15	0.00	1	2	G&L
A (2'-3')	2	2.11	2.11	0.00	0.00	1	2	G&L
A (3'-4')	2	2.11	2.11	0.00	0.00	1	2	G&L
A (4'-12)	2	2.11	1.96	0.00	0.15	1	2	G&L
A (12-5')	2	2.21	2.06	0.15	0.00	1	2	G&L
A (5'-13)	2	2.21	2.06	0.00	0.15	1	2	G&L
A (13-6')	2	2.21	2.06	0.15	0.00	1	2	G&L
A (6'-15)	2	2.21	2.06	0.00	0.15	1	2	G&L
A (15-7')	2	2.10	1.95	0.15	0.00	1	2	G&L
A (7'-8')	2	2.10	2.10	0.00	0.00	1	2	G&L
A (8'-9')	2	2.10	2.10	0.00	0.00	1	2	G&L
A (9'-16)	2	2.10	1.95	0.00	0.15	1	2	G&L
A (16-10')	2	2.13	1.98	0.15	0.00	1	2	G&L
A (10'-11')	2	2.13	2.13	0.00	0.00	1	2	G&L
A (11'-12')	2	2.13	2.13	0.00	0.00	1	2	G&L
A (12'-17)	2	2.13	1.98	0.00	0.15	1	2	G&L
A (17-13')	2	2.12	1.97	0.15	0.00	1	2	G&L
A (13'-14')	2	2.12	2.12	0.00	0.00	1	2	G&L
A (14'-19)	2	2.12	1.97	0.00	0.15	1	2	G&L
A (19-15')	2	2.10	1.95	0.15	0.00	1	2	G&L
A (15'-16')	2	2.10	2.10	0.00	0.00	1	2	G&L
A (16'-17')	2	2.10	2.10	0.00	0.00	1	2	G&L
A (17'-24)	2	2.10	1.95	0.00	0.15	1	2	G&L
A (24-18')	2	2.21	2.06	0.15	0.00	1	2	G&L
A (18'-27)	2	2.21	2.06	0.00	0.15	1	2	G&L
A (27-19')	2	2.11	1.96	0.15	0.00	1	2	G&L

Company: Company

Engineer: Name

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

9:31:45 a. m. 27/06/2025

Beam	Floor	L	Lu	a	c	Sec	Mat	System
A(19'-20')								
A(20'-21')	2	2.11	2.11	0.00	0.00	1	2	G&L
A(21'-31)	2	2.11	1.96	0.00	0.15	1	2	G&L
A'(6-1')	2	1.85	1.70	0.15	0.00	2	2	G
A'(1'-8)	2	1.85	1.70	0.00	0.15	2	2	G
A'(8-2')	2	2.11	1.96	0.15	0.00	2	2	G
A'(2'-3')	2	2.11	2.11	0.00	0.00	2	2	G
A'(3'-4')	2	2.11	2.11	0.00	0.00	2	2	G
A'(4'-12)	2	2.11	1.96	0.00	0.15	2	2	G
A'(12-5')	2	2.21	2.06	0.15	0.00	2	2	G
A'(5'-13)	2	2.21	2.06	0.00	0.15	2	2	G
A'(13-6')	2	2.21	2.06	0.15	0.00	2	2	G
A'(6'-15)	2	2.21	2.06	0.00	0.15	2	2	G
A'(15-7')	2	2.10	1.95	0.15	0.00	2	2	G
A'(7'-8')	2	2.10	2.10	0.00	0.00	2	2	G
A'(8'-9')	2	2.10	2.10	0.00	0.00	2	2	G
A'(9'-16)	2	2.10	1.95	0.00	0.15	2	2	G
A'(16-10')								
A'(10'-11')	2	2.13	1.98	0.15	0.00	2	2	G
A'(11'-12')	2	2.13	2.13	0.00	0.00	2	2	G
A'(12'-17)	2	2.13	2.13	0.00	0.00	2	2	G
A'(17-13')	2	2.13	1.98	0.00	0.15	2	2	G
A'(13'-14')	2	2.12	1.97	0.15	0.00	2	2	G
A'(14'-19)	2	2.12	2.12	0.00	0.00	2	2	G
A'(19-15')	2	2.12	1.97	0.00	0.15	2	2	G
A'(15'-16')	2	2.10	1.95	0.15	0.00	2	2	G
A'(16'-17')	2	2.10	2.10	0.00	0.00	2	2	G
A'(17'-24)	2	2.10	2.10	0.00	0.00	2	2	G
A'(24-18')	2	2.10	1.95	0.00	0.15	2	2	G
A'(18'-27)	2	2.21	2.06	0.15	0.00	2	2	G
A'(27-19')	2	2.21	2.06	0.00	0.15	2	2	G
A'(19'-20')	2	2.11	1.96	0.15	0.00	2	2	G
A'(20'-21')	2	2.11	2.11	0.00	0.00	2	2	G
A'(21'-31)	2	2.11	1.96	0.00	0.15	2	2	G
6(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
8(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
12(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
13(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
15(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
16(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
17(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
19(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
24(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
27(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
31(C-A)	1	8.06	7.56	0.25	0.25	3	2	G&L
6(B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
6(C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
6(A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
1'(B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
1'(A-A')	2	1.32	1.17	0.15	0.00	2	2	G
8(B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
8(C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
8(A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
2'(B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
2'(A-A')	2	1.32	1.17	0.15	0.00	2	2	G
3'(B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
3'(A-A')	2	1.32	1.17	0.15	0.00	2	2	G
4'(B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
4'(A-A')	2	1.32	1.17	0.15	0.00	2	2	G
12(B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
12(C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
12(A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
5'(B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
5'(A-A')	2	1.32	1.17	0.15	0.00	2	2	G

Company: Company

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

Engineer: Name

9:31:45 a. m. 27/06/2025

Beam	Floor	L	Lu	a	c	Sec	Mat	System
13 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
13 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
13 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
6' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
6' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
15 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
15 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
15 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
7' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
7' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
8' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
8' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
9' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
9' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
16 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
16 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
16 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
10' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
10' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
11' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
11' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
12' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
12' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
17 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
17 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
17 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
13' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
13' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
14' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
14' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
19 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
19 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
19 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
15' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
15' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
16' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
16' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
17' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
17' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
24 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
24 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
24 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
18' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
18' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
27 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
27 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
27 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L
19' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
19' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
20' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
20' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
21' (B'-C)	2	2.24	2.09	0.00	0.15	2	2	G
21' (A-A')	2	1.32	1.17	0.15	0.00	2	2	G
31 (B'-C)	2	2.24	1.99	0.00	0.25	1	2	G&L
31 (C-A)	2	8.06	7.56	0.25	0.25	1	2	G&L
31 (A-A')	2	1.32	1.07	0.25	0.00	1	2	G&L

FOUNDATION SOIL PROPERTIES

Number of soil properties = 1

Soil	Name	Pressure Distribution	Allowable gross pres. Pa T/m2	Increase Pa Combinations incl.EQ & WL (%)	MODULUS OF SUBGRADE REACTION	
					Gravity load Analysis, Kg T/m3	Lateral load Analysis, Ks T/m3
1	Soil1	Linear	7.4	33	400.0	400.0

* Values of subgrade reaction are used only on footings with rotations and/or vert-displac. permitted.

FOUNDATION BEAM DATA

Number of foundation beams = 31

Company: Company
Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

Engineer: Name
9:31:45 a. m. 27/06/2025

FOUNDATION BEAMS

Beam	Floor	L (m)	Lu (m)	a (m)	c (m)	TWidth (m)	Sec -	Mat -	Soil -	System -
C (6-8)	1	3.70	3.40	0.15	0.15	1.00	3	2	1	G&L
C (8-12)	1	8.44	8.14	0.15	0.15	1.00	3	2	1	G&L
C (12-13)	1	4.42	4.12	0.15	0.15	1.00	3	2	1	G&L
C (13-15)	1	4.42	4.12	0.15	0.15	1.00	3	2	1	G&L
C (15-16)	1	8.40	8.10	0.15	0.15	1.00	3	2	1	G&L
C (16-17)	1	8.52	8.22	0.15	0.15	1.00	3	2	1	G&L
C (17-19)	1	6.36	6.06	0.15	0.15	1.00	3	2	1	G&L
C (19-24)	1	8.40	8.10	0.15	0.15	1.00	3	2	1	G&L
C (24-27)	1	4.42	4.12	0.15	0.15	1.00	3	2	1	G&L
C (27-31)	1	8.44	8.14	0.15	0.15	1.00	3	2	1	G&L
A (6-8)	1	3.70	3.40	0.15	0.15	1.00	3	2	1	G&L
A (8-12)	1	8.44	8.14	0.15	0.15	1.00	3	2	1	G&L
A (12-13)	1	4.42	4.12	0.15	0.15	1.00	3	2	1	G&L
A (13-15)	1	4.42	4.12	0.15	0.15	1.00	3	2	1	G&L
A (15-16)	1	8.40	8.10	0.15	0.15	1.00	3	2	1	G&L
A (16-17)	1	8.52	8.22	0.15	0.15	1.00	3	2	1	G&L
A (17-19)	1	6.36	6.06	0.15	0.15	1.00	3	2	1	G&L
A (19-24)	1	8.40	8.10	0.15	0.15	1.00	3	2	1	G&L
A (24-27)	1	4.42	4.12	0.15	0.15	1.00	3	2	1	G&L
A (27-31)	1	8.44	8.14	0.15	0.15	1.00	3	2	1	G&L
6 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
8 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
12 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
13 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
15 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
16 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
17 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
19 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
24 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
27 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L
31 (C-A)	1	8.06	7.56	0.25	0.25	1.00	3	2	1	G&L

GROUND SUPPORT DATA

Total number of ground supports = 22

K = Spring constant(ton/cm)

Characteristics for All Degrees of Freedom
Value = K Dash = free C = constrained

Support	Floor	Type	Ux	Uy	Uz	TetX	TetY	TetZ
C-6	1	Fixed	C	C	C	C	C	C
A-6	1	Fixed	C	C	C	C	C	C
C-8	1	Fixed	C	C	C	C	C	C
A-8	1	Fixed	C	C	C	C	C	C
C-12	1	Fixed	C	C	C	C	C	C
A-12	1	Fixed	C	C	C	C	C	C
C-13	1	Fixed	C	C	C	C	C	C
A-13	1	Fixed	C	C	C	C	C	C
C-15	1	Fixed	C	C	C	C	C	C
A-15	1	Fixed	C	C	C	C	C	C
C-16	1	Fixed	C	C	C	C	C	C
A-16	1	Fixed	C	C	C	C	C	C
C-17	1	Fixed	C	C	C	C	C	C
A-17	1	Fixed	C	C	C	C	C	C
C-19	1	Fixed	C	C	C	C	C	C
A-19	1	Fixed	C	C	C	C	C	C
C-24	1	Fixed	C	C	C	C	C	C
A-24	1	Fixed	C	C	C	C	C	C
C-27	1	Fixed	C	C	C	C	C	C
A-27	1	Fixed	C	C	C	C	C	C
C-31	1	Fixed	C	C	C	C	C	C
A-31	1	Fixed	C	C	C	C	C	C

SUMMARY OF TOTAL FLOOR LOADS

LOAD CASE 1 : SELFW (D0)

Company: Company

Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

Engineer: Name

9:31:45 a. m. 27/06/2025

Floor	Force (ton)			Moment (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	0.00	0.00	191.10	0.0	0.0	0.0
1	0.00	0.00	47.46	0.0	0.0	0.0
Total	0.00	0.00	238.55	0.0	0.0	0.0

LOAD CASE 2 : DEAD (DL)

Floor	Force (ton)			Moment (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	0.00	0.00	182.11	0.0	0.0	0.0
1	0.00	0.00	0.00	0.0	0.0	0.0
Total	0.00	0.00	182.11	0.0	0.0	0.0

LOAD CASE 3 : ROOF L (RFL)

Floor	Force (ton)			Moment (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	0.00	0.00	73.05	0.0	0.0	0.0
1	0.00	0.00	0.00	0.0	0.0	0.0
Total	0.00	0.00	73.05	0.0	0.0	0.0

LOAD CASE 4 : EQUAKE X (EQX) - TYPE : SPECTRAL

Floor	Force (ton)			Acc. Tors. Mom. (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	268.04	0.00	0.00	0.0	0.0	155.7
1	0.00	0.00	0.00	0.0	0.0	0.0
Total	268.04	0.00	0.00	0.0	0.0	155.7

LOAD CASE 5 : EQUAKE Y (EQY) - TYPE : SPECTRAL

Floor	Force (ton)			Acc. Tors. Mom. (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	0.00	266.25	0.00	0.0	0.0	873.8
1	0.00	0.00	0.00	0.0	0.0	0.0
Total	0.00	266.25	0.00	0.0	0.0	873.8

LOAD CASE 6 : WIND X (WLX)

Floor	Force (ton)			Moment (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	0.99	0.00	0.00	0.0	0.0	0.6
1	0.68	0.00	0.00	0.0	0.0	0.0
Total	1.67	0.00	0.00	0.0	0.0	0.6

LOAD CASE 7 : WIND Y (WLY)

Company: Company
Project: IE HECTOR MANUEL VIDES BALLESTEROS (MÓDULO 5)

Engineer: Name
9:31:45 a. m. 27/06/2025

Floor	Force (ton)			Moment (ton-m)		
	Px	Py	Pz	Mx	My	Mz
2	0.00	6.76	0.00	0.0	0.0	23.3
1	0.00	0.00	0.00	0.0	0.0	0.0
Total	0.00	6.76	0.00	0.0	0.0	23.3

SUMMARY QUANTITY OF MATERIALS

COLUMNS

Item	Section	Material	Length m	Weight/Len ton/m	Total Weight ton
1	C-30X50	RConcrete2	55.55	0.360	20.00
TOTAL =					20.00

BEAMS

Item	Section	Material	Length m	Weight/Len ton/m	Total Weight ton
1	VG-30X60	RConcrete2	250.36	0.432	108.16
2	VG-20X60	RConcrete2	199.65	0.288	57.50
TOTAL =					165.65

FOUNDATION BEAMS

Item	Section	Material	Length m	Weight/Len ton/m	Total Weight ton
1	VC-30X45	RConcrete2	213.95	0.324	69.32
TOTAL =					69.32

SLABS

Item	Section	Material	Area m²	Weight/Area ton/m²	Total Weight ton
1	Cubierta Plana w =2.4		233.25	0.300	69.98
2	Cubierta Liviana w =2.4		528.09	0.024	12.67
TOTAL =					82.65